220

CHITALDROOG DIVISION.

ADVERTISEMENT.

The 22nd July 1889.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldroog Division, up to 30th August 1889, for constructing a new Taluk Cutcherry at Molkalmuru. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1890.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldroog between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Details.	Per.	Quantity.	Rates to be offered by the Tenderer.
Stone in chunam	C. Ft.	12,188	
Brick in chunam	Do	21,044	
Slab stone work	Do	379	
Archwork	Do	695	
Cornice work	R. Ft.	1,128	
Plastering	Sq.	286·63	
Whitewashing	Do	156·00	
Colorwashing	Do	129·00	
Roofing with Mangalore tiles, teak reapers, &c.	Do	70·24	
Flat terrace roofing	Do	1·56	
Bengal terrace	Do	13·32	
Concrete flooring including plastering..	Do	42·02	
Gravel flooring	C. Yd.	8	
Woodwork teak	C. Ft.	521	
Earthwork foundation excavation	Do	522	
Filling in basement	L. S.	..	
Iron wrought	L. S.	373	
Painting chocolate	Sq.	28·74	
Wood oiling 2 coats	Do	41·48	
Bamboo matting	Do	28·87	
Doors to Treasury room 3 × 6 with iron, &c.	E.	1	
Do small 3′ × 6′ pannelled	Do	17	
Do do battened	Do	5	
Do large 5′ × 6′ do	Do	1	
Windows large 4′ × 5′ iron bars, &c.	Do	4	
Do small 3′ × 4′ do	Do	12	
Do Ventilators 1½′ × 3½′ do	Do	2	
Do Pannelled 3′ × 4′ iron bars	Do	10	
Do Battened 3′ × 1½′ do	Do	7	
Do do 2′ × 1½′ do	Do	9	
Zinc Gutters at valleys	F. Ft.	60	

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government promissory notes as earnest money, and be superscribed "Tender for constructing a new Taluk Cutcherry at Molkalmuru"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

D. RANGA RAO,
Offg. Executive Engineer.